ENGINEERING DEPARTMENT

BANGALORE DIVISION.

Abstract Notification dated 1st September 1938.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for the maintenance work to Jodi Aradasanahalli Tank of Devanhalli Taluk, published in pages 1541-1543 of Part VI of the *Mysore Gazette*, dated 8th September 1938.

2. The last date for the receipt of the tenders is 2 P.M. on 27th September 1938. Duplicate challan for having credited the deposit amount of Rs. 250 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

Notification dated 13th September 1938.

It is hereby notified for the information of the General Public that old stores will be sold by public auction on the 28th September 1938 at 8 A.M. in the premises of the Office of the Executive Engineer, Bangalore Division, Bangalore. The terms and conditions of the sale are :—

(*a*) The articles will be sold in lots and knocked down to the highest bidder. In the event of any dispute arising between two or more bidders offering the same price, the lot or lots shall be put up again and resold.

(*b*) All articles purchased shall be at the risk of the purchaser thereof from time of sale.

(*c*) Cash shall be paid in full for lots purchased by bidders before delivery and the articles shall not be permitted to be removed from the place of auction until the sale is confirmed by the Executive Engineer.

(*d*) In case of default of payment of purchase money by any bidder, the articles shall be resold at the risk and cost of the bidder who shall also be liable to make good any losses arising thereby.

The following is the list of articles available for Sale :—

ARTICLES OF CHANNAPATNA TRAVELLERS' BUNGALOW.

Wooden Cot with iron strap	1	Tea Pots	2
Hurricane lanterns	1	Enamel Coffee Kettle	1
Mirror Stand	1	Big Spoon	1
Enamel Soup Tray	2	Desert plate	1
Grills	2	Dinner plate	3
Carving fork	1	Aluminium vessel with cover	7
Glass Tumbler ½	1	Iron fraying pan with handle	3
Glass Tumbler ¾	1	Brass Spoon	2
Egg Cups	4	Aluminium Tumbler	4
Round Iron Steel File	1	Aluminium Spoon	2
Narrow Bone Spoon	1	Brass Basin	1
China Plates	4	Knife	2
Cup and Saucers	4		

ARTICLES OF INSPECTION LODGE AT HOSAKOTE.

Arm Chair	1	Enamelled Dinner Plates	3
Bug Proof Chair	1	Soup Plates	5
Commode with stand	3	Iron Kettle	1
Candle Stand with two Chimneys	3	Salt Cellar	1
Hanging Lamp	2	Enamel Dish	1
Wall Lamps	2	Bath Tubs	2
Zinc Buckets	2	Wine Glass	1
Enamel Jug	1	Enamel Basin	1
Camp Table Old	1	Aluminium Vessels	3
Spring Cover	2	Soap Trays	2
Iron straps big and small	42	Copper Hande	1
Iron brass big and small	10	Kolaga Thappale	2
Kitchen knife	1	Brass Thappale	1
Table Knife	1	Brass Chamboo	1
Cups white	11	Bindige	3
Water Jug	1	Iron Jali Soutu	1
Milk Jug	1	Grid Iron	1
Sugar Bowl	1	Iron frying pan	2
Egg Cup	3	Aluminium Tumbler	2
Enamelled Tea Pots	1	Deepastambha	1
Enamelled Plates	2	Eeligemane	1

Notification dated 17th September 1938.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 17th October 1938, for restoring Anekal Rajankere Register No. 10 of Anekal Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for restoring Anekal Rajankere". The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the treasury the deposit amount of Rs. 160 under 17 (a) Public Works Deposits or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such of the tenderers as wish to be present on 17th October 1938 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract form, after depositing an additional sum of Rs. 160 for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore Division, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.'

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of April 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 160 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for restoring Anekal Rajankere, Reg. No. 10 of Anekal Taluk.

Serial No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
	Bund R. L. 55·00.			Rs. a. p.	Rs.	Rs.
1	Clearing jungle with roots	Grade	25	1 8 0		
2	Cutting steps and grips on bund and slopes	,,	25	1 0 0		
3	Earthwork to bund with a required lead, lift and consolidation	C.yd.	3,700	0 3 6		
4	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	4,300	0 0 10		
5	Dismantling old stone work ..	C.yd.	176	0 4 0		
6	Rough stone revetment new with the required lead, lift, jelly backing and jelly wedging, etc., complete ..	,,	289	2 0 0		
7	Resetting old stone revetment with the required new jelly backing and jelly wedging, etc., complete	,,	160	0 8 0		
8	Fixing old grade stones on new bed slabs and painting and figuring, etc. ..	Each	25	0 8 0		
9	Providing and fixing new index stones.	,,	25	0 6 0		
10	Refixing old B. M., Register and Gauge Stones on new bed slabs, including painting and figuring	,,	3	1 0 0		
11	Providing and fixing new B. M. stones on bed slabs with figures chiselled and painted	,,	1	3 0 0		

Serial No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.	Rs.	Rs.
	Feeder Channel.					
1	Earthwork cutting or embankment with proper slopes	C.yd.	4,166	0 3 0		
2	Rough stone work for drops ..	,,	15	2 0 0		
	Right Waste Weir R. L. 50.00 length (54 plus 36) 90 feet.					
1	Earthwork excavtaing foundation ..	C.yd.	12	0 3 0		
2	Burnt brick in surki mortar ..	C.ft.	350	0 4 9		
3	Burnt stone slabs one line dressed and fixed in surki mortar	S.ft.	63	0 6 0		
4	Providing joggle joints in slabs ..	Each joint.	5	1 0 0		
5	Plastering with surki mortar ..	Sqr.	3.36	4 0 0		
6	Rough stone apron new with the required lead, jelly backing and jelly wedging, etc., complete	C.yd.	40	2 0 0		
7	Earthwork cutting draft channel for apron	,,	188	0 3 0		

Tender Notice dated 17th September 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 18th October 1938, for restoring the breached Manigenahalli Tank Reg. 89 of Magadi Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for the restoring the breached Manigenahalli Tank, Magadi Taluk". The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the treasury the deposit amount of Rs. 170 under "17 (a) P. W. Deposits" or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 18th October 1938 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form after depositing an additional sum of Rs. 170 for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.,

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of April 1939, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 170 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(a) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for restoring the breached Manigenahalli Tank, Reg. No. 89 of Magadi Taluk.

Serial No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
	Bund.			Rs. a. p.	Rs.	Rs.
1	Clearing jungle including roots ..	Grade	17	1 8 0		
2	Cutting grips and trenches	,,	17	1 0 0		
3	Earthwork to bund with the required lead, lift and consolidation ..	C.yd.	3,666	0 4 0		
4	Rough stone work with the required lead, lift, jelly backing and jelly wedging, etc., complete	,,	428	1 8 0		
5	Gravel backing behind revetment with the required lead, lift and consolidation	,,	127	0 9 0		
6	Removing and resetting old stone revetment with new jelly backing and jelly wedging	,,	150	0 12 0		
7	Puddle wall with the required lead and a mixture of equal quantity of clay and gravel well kneaded ..	,,	341	0 8 0		
8	Burnt brick in surki mortar for core wall	C.ft.	1,575	0 5 0		
9	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	2,491	0 1 0		
10	Providing and fixing grade stones on bed slabs with figures chiselled and painted	Each	17	1 8 0		
11	Do Register No. Stone do ..	,,	1	3 0 0		
12	Do B. M. Stone do ..	,,	2	3 0 0		
13	Do Gauge Stone do including masonry all round ..	,,	1	14 0 0		
14	Do Index Stone	,,	17	0 6 0		
	Waste Weir.					
1	Earthwork excavating foundation ..	C.yd.	77	0 4 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	416	0 4 0		
3	Burnt brick in surki mortar ..	,,	759	0 5 0		
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar ..	S.ft.	1,080	0 6 0		
5	Surki mortar plastering ..	Sqr.	10.89	1 0 0		
6	Rough stone work new with the required lead, lift, jelly backing, jelly-wedging, etc.	C.yd.	109	1 8 0		
	Pipe Sluice at R. L. 44.00.					
1	Earthwork, cut-opening the bund and forming a ring bund in front ..	C.yd.	249	0 3 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	234	0 3 9		
3	Burnt brick in surki mortar ..	,,	506	0 4 6		
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar ..	S.ft.	178	0 6 0		
5	Providing and fixing jally wood plug and iron rod 2"×$\frac{3}{8}$" in section with locking arrangements, etc., complete	Each	1	15 0 0		
6	Cutting holes in slab	,,	4	1 0 0		
7	Plastering with surki mortar ..	Sqr.	6.86	3 4 0		
8	Refilling the cut earth including consolidation	C.yd.	249	0 4 0		
9	Removing and resetting old stone work with new jelly backing and jelly wedging	,,	18	1 0 0		
10	Providing, laying and jointing with cement 6" dia., C. I. Bhadravati pipes	R.ft.	35	2 8 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.